

BOARD REPORT on the Messrs. Hawthorn Leslie & Co. Yard No 596.

225.0 x 33.0 x 16.5.

1. As a full-scauthing vessel having standard sheer & camber, and erection of the length proposed, the height of the raised quarter-deck being, however, equal to the standard height, summer moulded draught = ~~14'-10 1/4"~~ 15'-0 3/4"
2. As a full-scauthing vessel having proposed erection, sheer & camber, summer moulded draught = 15'-2"
3. As a full-scauthing vessel having standard sheer & camber, and a raised quarter-deck of standard height, for a summer moulded draught of 15'-2", the percentage length of erection = 62.4

Copy to Mr. Lott.

87-B.

27.11.34

28

003252-003262-0030