

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

Enclosures.

21st November, 1950

Dear Sirs,

s.s. "KIRUNA"

Eng.

I am in receipt of your letter of the 20th October enclosing plans Nos. 184160, 184161, 184162, 184163, 184164 and 184202 in connection with the oil fuel installation proposed to be fitted to the above vessel.

In reply I have to inform you that these plans of General Pumping Arrangement and Pumping Arrangements in Machinery Space have been examined and will be approved, provided the arrangements be as shown and amended thereon and the remaining requirements of the Rules for Pumping and Piping be complied with so far as they are applicable.

I have to point out that in order to comply with the requirements of the new Rules for Pumping and Piping the cross sectional area of the air pipes to tanks carrying oil fuel should be not less than one and a half times that of the filling pipes.

It is noted from the above plans that it is proposed to remove a W.T. Bulkhead on 66 Frame. Due to the removal of this bulkhead, the deck supports in way would require to be examined, and it is assumed this will be done in your Office.

herewith.

One set of the drawings is returned

Yours faithfully,

pro Secretary

The Surveyors,
GOTHENBURG.

003263-0032 74-0095