

3m.9.5

1951 MAR 30

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

GB

VESSEL'S NAME

'K I R U N A'

REPORT

Got.

No. 18059

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

The class is subject to sternframe solepiece (E.W. & reinforced 3.49 & previously) being specially examined at next drydocking.

ACTION is DEFERRED until 10.50 for Special Survey.

The GOTHENBURG Surveyors report (2.51), ship examined on floating dock, bottom coated, and on account of damages, causes not known, repairs effected to a number of shell plates, frames, etc.

The requirements of a PERIODICAL SPECIAL SURVEY (C), due 12.49, complied with and a number of wear and tear repairs effected. 30 fathoms of chain cable renewed and verified

The ship has been converted for oil fuel burning involving the construction of oil fuel and settling tanks in the original coal cross bunker space, and the modification of D.B. tanks Nos. 3, 3A & 4, all in accordance with plans approved.

An approved arrangement of widely spaced pillars and girders at centreline has been built in the hold spaces in accordance with plan approved.

An escape trunk from the tunnel recess has also been constructed inside the A.P. tank in accordance with plan approved.

The sternframe solepiece, as above, specially examined and found efficient.

IT IS SUBMITTED this ship is worthy to remain as classed, with record of docking 1.51 and to have notation of 'ss. Got. 2.51' assigned as recommended, subject as above.

1.51 Got.)
ss. Got. 2.51) Subject

INSERT IN R.B.

✓ Fitted for oil fuel 2.51, F.P. above 150°F"
AMEND R.B. (Col.12)

✓ FROM - 5 BH to U ~~ss~~ dk.
TO - 6 BH to U ~~ss~~ dk.

FROM - Cem.
TO - pt Cem.



© 2020
28
3
51

Lloyd's Register
Foundation

2.51. FP above 150°F." to be made in the Register Book.

Survey Fee (per Section 29)

Kr. 1220:00

Fees applied for,