

# Lloyd's Register of Shipping.

Ship's Name "KIRUNA"

Official No. 6479

*Memorandum of alterations reported since ship was surveyed for assignment of Load Lines*  
in \_\_\_\_\_

One oiltight access manhole (p. & s) to bunker tanks fitted  
on shelter deck, 600 x 650 mm., Coamings 230 x 8 mm, Cover: Steel 13 mm with  
 $\frac{3}{4}$ " bolts, Spacing: 95 mm apart.

Deck plating efficiently compensated in way.

1st February, 1951



© 2020

Lloyd's Register  
Foundation

003263-005274-0131