



S.S. "King Edgar"Mach Survey (continued):-

Boilers & mountings opened out and examined internally and the super heaters examined; sundry minor repairs effected and the safety valves adjusted under steam.

Repairs (To Owner's account):- (See also Cardiff Rpt N° 55769):

M.P. piston head removed from cylinder & retained on board as spare. A new piston head & rings fitted.

H.P. - M.P. cylinder coning joint bolts hardened up. Repairs examined under steam & found satisfactory.

General service pump liners rotated & buckets renewed.

Boiler & evaporator flow down shell plate over rings renewed, with efficient tap bolts.

The inter shafting has been verified & found in accordance with Glasgow F.E. Rpt N° 69647.

A F.E. Rpt concerning the pumping arrangements is forwarded herewith.

AMBE. *LB*



© 2020

Lloyd's Register  
Foundation