

"EMPIRE MIRANDA"
- - - - -

LITHGOWS 983.


The makers' test certificate for generator No. 110T415 supplied by the Admiralty shows temperature rise from the armature in excess of that permitted by the Rules. The makers state that the temperature rise will not exceed 63°F if the rating is reduced to 13 KW.

It is recommended that the rating of this generator be reduced to 13 KW. subject to a satisfactory temperature test being carried out on the generator at this new rating, the name plate altered accordingly and a red line marked on the ammeter at 118 amps.

The Electrical Equipment of this vessel has been fitted on board under special survey in accordance with the requirements of the M.O.W.T. except as stated above, tested under full working conditions and found satisfactory. The materials and workmanship are good.

The report is in the hands of the Builders for signature.

For: R. Murchison.



11th May, 1943.



© 2020

Lloyd's Register
Foundation

003298-003308-0277