

# Lloyd's Register of Shipping.

Ship's Name "MERCHANT".

Official No. 169501.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Conversion from Coal to Oil Burning.

Vessel now converted from coal to oil burning.

Coal cross bunker now three oil deep tanks with double bottom below and port and starboard wing bunkers in tween decks, settling tanks port and starboard at sides of fidley casing in tween decks. ✓

O.T. hatches fitted on upper decks, 2 port and 2 starb. to tween deck wing tanks and settling tanks, each 20" dia. ✓

Coamings 6" high x  $\frac{3}{8}$ " fabricated angles inverted welded to deck with bolted covers on flanges of angles. ✓

The following air pipes now fitted all 24" to underside of mouth of G.N. and fitted with wire gauze:- 5 @ 6" dia. and 3 @ 4" dia. on upper deck. ✓

The wing bunker hatches on the upper deck have been completely removed and openings plated in 2 @ 15' 6" x 3' 0". ✓

*J. Simpson*

SURVEYOR TO LLOYD'S REGISTER.

Liverpool. 22nd December, 1947.

*Maked*  
*J. Simpson*  
4 FEB 1948

