

Lloyd's Register of Shipping.

Simpang 4,

Sourabaya, 13th October, 1939.

LLOYD'S REGISTER
Received
- 6 DEC 1939
Ansd. X
LONDON



Dear Sir,

I have to confirm my cablegram of the 9th instant about the steamship "TJIBADAK" No.35191 in Register Book reading:

"(LCD") LLOYDS REGISTER WOKINGHAM
TJIBADAK WHAT REINFORCEMENTS DEEPTANKS MOLASSES
ALTERNATIVE TWEENDECKS SEPARATE VROUWES"

and your reply that reached me to day reading:

"(DLT) VROUWES SIMPANG 4 SOURABAYA
TJIBADAK IF NOTATION REQUIRED DENOTING DEEP TANKS
SUITABLE CARRIAGE MOLASSES HOLD BULKHEAD WEBS AND
GIRDERS REINFORCED BY TWELVE BY POINT FIVE INCHES
AND THREE AND HALF BY POINT FIVE FACE PLATES RES-
PECTIVELY STOP SPAN ALTERNATE HOLD STIFFENERS
REDUCED BY BRACKETS FITTED UNDER GIRDER STOP
REVERSED BARS TO ALTERNATE TWEENDECK STIFFENERS
STOP SAME REINFORCEMENT FOR TWEENDECK TANK IF
SEPARATE LLOYDS REGISTER."

It will now be further considered whether or not these reinforcement will be carried out.

I am, Dear Sir,
Yours faithfully,



Lloyd's Register
Foundation

The Secretary

LONDON.
Wokingham.

003311-003320-0015

Vertical stamp on the right edge of the page.

