

COPY.

H  
Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

11th October, 1939.

Dear Sir,

I have to confirm the following telegrams  
which have passed between us regarding the S.S. "TJIBADAK" :-

Received -

"TJIBADAK WHAT REINFORCEMENTS DEEP TANKS MOLASSES ALTERNATIVE  
"TWEEN DECKS SEPARATE"

Sent -

"TJIBADAK IF NOTATION REQUIRED DENOTING DEEP TANKS SUITABLE  
"CARRIAGE MOLASSES HOLD BULKHEAD WEBS AND GIRDERS REINFORCED  
"BY TWELVE BY POINT FIVE INCHES AND THREE AND HALF BY POINT  
"FIVE FACE PLATES RESPECTIVELY STOP SPAN ALTERNATE HOLD  
"STIFFENERS REDUCED BY BRACKETS FITTED UNDER GIRDER STOP  
"REVERSED BARS TO ALTERNATE TWEENDECK STIFFENERS STOP SAME  
"REINFORCEMENT FOR TWEENDECK TANK IF SEPARATE".

I am, Dear Sir,

Yours faithfully,

Secretary.

V. F. Vrouwes, Esq.,

SOURABAYA.



© 2020

Lloyd's Register  
Foundation

003311-003320-0016