


"TJIBADAK"

Submitted the Surveyors be informed by  
wire as follows :-

"TJIBADAK IF NOTATION REQUIRED DENOTING DEEP TANKS SUITABLE  
"CARRIAGE MOLASSES HOLD BULKHEAD WEBS AND GIRDERS REINFORCED  
"BY 12 BY POINT 50 INCHES AND THREE AND HALF BY POINT 50  
"FACE PLATES RESPECTIVELY STOP SPAN ALTERNATE HOLD STIFFENERS  
"REDUCED BY BRACKETS FITTED UNDER GIRDER STOP REVERSED BARS  
"TO ALTERNATE TWEENDECK STIFFENERS STOP SAME REINFORCEMENT  
"FOR TWEENDECK TANK SEPARATE".

*Del. 10.10.39*  
*Amend. 11.10.39 (Del. 7th)*



11th October, 1939.



© 2020

Lloyd's Register  
Foundation

003311-003320-0018