



# Lloyd's Register of Shipping

707 American National Insurance Building

GALVESTON, TEXAS

January 21st, 1949.

Principal Surveyor

NEW YORK

Dear Sir:

"TROCHURUS"  
Gal. 5031

In reply to your letter of the 6th inst regarding the repairs to the bulkhead of the above Vessel.

1 - 8" fracture drilled at ends, veed out and welded in transverse bulkhead between No. 5 and 6 tanks.


1 - 12" fracture drilled at end, veed out and welded in transverse bulkhead between No. 6 and 7 center tanks.

1 - 9" fracture drilled at ends, veed out and welded in transverse bulkhead between No. 7 and 8 center tanks.

1 - 18" fracture drilled at ends, veed out and welded and longitudinal bulkhead between No. 5 center and No. 5 starboard wing tanks.

Tanks tested to rule requirements and repairs found or made tight.

Yours very truly, .

  
JAMES FINDLAY



© 2020

Lloyd's Register  
Foundation

003328-003332-0020