

"THELIDOMUS"

AND

"TENAGODUS"

The equipment letter for this type of tanker has been taken out and is gt.

IT IS SUBMITTED the Owner's be informed the Rule requirements are as follows:-

3 bower anchors of 271 cwts. collective weight (stockless).

1 stream anchor, 28 cwts. (ex.stock).

330 fms. 2 $\frac{5}{16}$ " dia. wrought iron, or 2 $\frac{5}{16}$ " special steel, stud chain cable.

120 fms. 1 $\frac{5}{16}$ " stream chain or 5 $\frac{1}{2}$ " 6 x 24 Special flexible steel wire rope.

130 fms. 6 $\frac{1}{2}$ " Special flexible steel wire towline.

2 x 100 fms. 8" hemp or 2 $\frac{3}{4}$ " 6x12 flexible steel wire hawsers.

2 x 100 fms. 8" hemp or 2 $\frac{3}{4}$ " 6 x 12 flexible steel wire warps.

CRM.

11-11-47.

[Signature]

It is further submitted the Owners be informed the anchor & cable equipment reported on board 9,47, consists of

Starboard bower anchor	11,420 lbs. (stockless)
Port " "	11,860 "
Starboard " "	11,420 "
Starboard anchor	4308 "
270 fms. 2 $\frac{5}{16}$ " H.T. stud chain cable.	"

© 2020

Lloyd's Register
Foundation

003328-003332-0239