

# Lloyd's Register of Shipping.

Ship's Name "BACTRIA."

Official No. 160411

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Forecastle space:- Accommodation now modified at this time, the centre steel door removed and opening plated in. Three steel doors replaced by three hinged wood doors. (Wing steel doors Port and Starboard not altered).


Bridge space aft end:- Accommodation now modified at this time, tonnage opening fitted at centre of bridge end with portable plate and hook bolts. One bridge end opening plated over and two hinged W.T. doors fitted, 1 port and 1 starb., openings 5' 0" x 2' 0" with 18" sill. Steel companion of strong construction fitted on after end of bridge deck, hinged wood door opening 5' 0" x 2' 0" with 12" sill, 10" port on fore side, 10" M.T. fixed vent on top.

3 additional cowl ventilators fitted to bridge deck aft 2 @ 9" diameter x .32", coaming 33" high, and 1 @ 6" diameter x .30" coaming 30" high, provided with wood plugs and canvas covers.

4 portlights fitted to ship's side, 2 port and 2 starb., complete with hinged dead-lights.

Freeboard certificate and copy amended to suit new closing appliances in forecastle front and bridge end.

ML-D



SURVEYOR TO LLOYD'S REGISTER.

Liver pool. 15.4.47.

Noted  
E.C.  
30.4.47



© 2020

Lloyd's Register  
Foundation