

For the information of Surveyors and the Committee only.

Received at _____ Office, _____ 19

Lloyd's Register of British & Foreign Shipping.

(Report on Vessel No. 7237 Port TRIESTE)

No. 1138 SHIP ~~FORGINGS OR~~ CASTINGS.

I have to report that the undermentioned ~~Iron or Steel Forgings or Castings~~, manufactured by Messrs. Withon, Forgl., Eisenh. Ven. of Withowitz for the Vessel No. 105, being built by Messrs. Cantenavale Triestino of Morfolame have been inspected by me as set forth below and found to be, so far as can be seen, sound and free from defects

- 1 Rudder frame (Plate fitted)
- 1 Rudder post

Work on Forgings or Castings.

Lloyd's
No. 1060
M.C. 1.21

Vienna 20th January 1921
M. Wood

	STERN FRAME.	RUDDER FRAME.		Rudder STEM Post		
Material*	/	annealed S.M. Steel		annealed S.M. Steel		
How made		cast		cast and drawn out		
Dimensions		235x200/190x162		ø 240		
Progress on Inspection		finished		finished		
Date when Inspected		29/5.20; 9/11.20; 14/1.21		12/7.20; 8/9.20; 14/1.21		
CASTINGS.				forged part	cast part	
Tests on Standard Test Pieces.						
Stable Test—						
Tons per square inch			28.3	28.1	29.6	28.3
Extension per cent. ... 3"			31.6	32.8	31.6	25.0
Bending Test—		180° closed, satisfactory		180° closed, satisfactory		
Angle before fracture		7 1/2°, satisfactory according to Rules, found satisfactory		10°, satisfactory according to Rules, and found satisfactory		
Impact Test—						
Height from ground						
Numbering Test—						
If made according to Rules and found satisfactory ...						

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

Fee (if any chargeable) £ _____
To be paid at Vienna

If of Iron, state whether scrap or puddled Iron. If of steel, state whether made on the Open Hearth process.

003357-003368-0187

© 2020

Lloyd's Register Foundation