

FREEBOARD REPORT on the

"Empire Baron"

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, ^{subject to} the ventilator coamings 56" in height on the fore-castle and throat 8'-10" in height on the poop deck being specially supported;

the gauge closing the airpipes being renewed where defective, or replaced by efficient closing appliances means of closing;

the circular bolted plate on the hull armed ships, 12" below the freeboard deck, being secured watertight if this is not already the case;

It is concluded that the wash-basin discharges armed ships which have no storm-valves are ~~from spaces on the bridge~~ ^{on the bridge} appliances situated on or above the bridge deck, but the surveyors should confirm this.

The assignment letter should be sent to the LONDON Surveyors.

87-B

30-12-41

003357-003368-0218

© 2020

Lloyd's Register
Foundation