

# Lloyd's Register of Shipping,

Empire House, Mount Stuart Square,

Cardiff, 28th November 1932.



Dear Sir,


With reference to your freeboard assignment letter dated the 7th October, 1932, for the steamer "PENCARROW", we enclose the verification form and beg to report that the necessary conditions have been complied with as follows:-

- (1) Canvas covers have been provided for closing all air pipes.
- (2) Suitable provision has been made for rigging lifelines for use in the wells.

The wood door to the starboard tonnage opening in the forecastle bulkhead has now been removed and 3" shifting boards fitted full height, while the wood door to the port tonnage opening remains in place, the framing of this door being 2 1/4" thick and the panelling consisting of two thicknesses of 1" boards worked diagonally across one another.

The tap bolts securing the bridge front doors pass through the doors and are tapped into the bulkhead plating.

All the fastenings of the portable plates to the openings in the bridge after bulkhead pass through the



S.S. "PENCARROW".

plates only.

We are, Dear Sir,

Yours faithfully,

for the Surveyers,

E. Brimblecombe.

The Secretary,  
LONDON.



© 2020

Lloyd's Register  
Foundation

40-0 40 9-6

LENGTH  
63  
60  
63  
- Ta  
(if r  
- 1/4  
N DEC  
vered .  
UND OI  
ng  
subject  
Lance  
a fe  
each p  
have  
eter  
H  
S  
6-0129  
ships, meas  
taken at  
side.

Referred to the Chief Ship Surveyor.  
(Freeboard).

*WJH*

29 NOV 1932

*Particulars of Alterations noted in report.  
Submitted to Certificate Copy to be forwarded  
to the Cardiff Surveyors for issue*

*29/11/32*

*RM*

*Handwritten notes*

*Vertical stamp or text*

LLOYD'S REGISTER  
LONDON



© 2020  
Lloyd's Register  
Foundation

1932  
LONDON  
LLOYD'S REGISTER  
FOUNDATION