

30 APR 1945

Rpt. C. 11 (Contd.)

Index No. 30307

# Lloyd's Register of Shipping. Hld 5856<sup>n</sup>

Ship's Name T.S.S. "LARGS BAY".

Official No. 137225.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations have been carried out to Sea Transport instructions at this time:-

The two existing wood booby hatches on No.6 Hatch have been removed and replaced by 2 steel booby hatches.

Wood doors fitted and are of strong construction.

The fore end of No.3 Hatch on the Promenade deck has been plated in and two ventilators with fixed tops fitted on same.

Battening arrangements modified as necessary.

Ventilators 29" x 12" x 30" high of substantial construction and adequately supported.

Access hatch from No.3 Hold plated over and ventilator fitted on top of hatch

16" x 16" x 4'6" of substantial construction and adequately supported.

1 flap on skid skylight forward of No.3 hatch plated over and ventilators fitted on top 17" x 17" x 4'3" high of substantial construction and adequately supported.


Access hatch from No.2 hatch plated in and new vent fitted.

Coaming 24" x 12" dia. x 40" thick, with fixed top.

*S.B. Lumsden*

SURVEYOR TO LLOYD'S REGISTER.

*Noted  
30 APR 1945  
JPS*



© 2020

Lloyd's Register  
Foundation

003385-003390-0206