

7 MAR 1941

UPPER DECK

COAL BUNKER

7700 AT HATCH #2  
7350 " " " "

ROUND OF BEAM .260"

FRAMES

- SIDE FRAMES IN AFTER PEAK #6-AFT = 120x75x9 1/4" ✓  
- " - " - ENGINE ROOM #7-21 = 170x90x10 ✓  
- " - " - BOILER #23-34 = 170x90x11.5 ✓  
- " - " - HOLD #36 = 170x90x11.5 ✓  
- " - " - " #37-74 = 210x90x11.5 ✓  
- " - " - " #76-99 = 180x90x11.5 ✓  
- " - " - " #100-106 = 180x90x12.5 ✓  
- " - " - " #107-113 = 215x90x10 ✓  
- " - " - FORE PEAK #115-FORM = 120x75x8 1/2 ✓

DOUBLE BOTTOM.

SOLID FLOORS TO BE FITTED ON EVERY FRAME IN THE ENGINE ROOM UNDER BOILER BEARERS, BULKHEADS AND FORWARD OF 75' OTHERWISE ON EVERY THIRD FRAME BRACKET FLOORS TO BE FITTED ON REMAINING FRAMES.

BRACKET 9 1/4" IN DR 11 1/2" 19 1/4" RIV

65 1/2" CEILING ON 40 1/4" BATTENS 75 1/2" FLANGE

QUICK WELDED ALUMINUM FRAMES IN PAINTING AREA

THE SHELL AND ACTUAL

A KEEL 1105x165 1/2" FOR 7/8" 15 1/2" AT ENDS

B 11 1/2" FOR 7/8" 10 1/4" AT ENDS

C 11 1/2" FOR 7/8" 10 1/4" AT ENDS

D 11 1/2" FOR 7/8" 10 1/4" AT ENDS

10 1/2" IN BOILER ROOM 8 1/2" IN ENGINE " AND FOR 0.25 L FROM STEM. 7 1/2" FOR OTHERS.

DETAIL A

SOLID FLOORS IN ENGINE SPACE

13 1/4" IN BOILER ROOM a=10.3  
10 1/2" ENGINE a=8.5  
10 1/2" FOR 7/8" a=8.5  
9 1/4" AT ENDS a=7

CORRECTED AS APPROVED BY GERMANISCHER LLOYD DATED BERLIN THE 30TH OF JUNE 1941

Class 100 A 1

GÅLLE VARVS OCH VERKSTADS NYA AB

N 264

ad 7.3.41

SUPPLEMENT TO DRAWING

MIDSHIP SECTION

SCALE 1:25

"NARVA"

003385-003390-0251


© 2020

Lloyd's Register Foundation

Narva

<sup>12</sup>  
(10 plans)

Advised in the 5<sup>th</sup> (blessed)  
d/d 10/6/57

"NARVA" \*

Thy to midship section.

2

RETAIN



© 2020

Lloyd's Register  
Foundation

003385-003390-0251 1/2