

2 DEC 1953

44051
Index No.

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name "TEESWOOD"

Official No. 169160

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in September 1953.

Alterations to Ventilators.

UPPER DECK:-

18" dia ventilators at aft end of No 1 hatch P.S., to No 1 hold, and abreast fore end of No 2 hold P.S., (aft of Bridge house) to No 2 hold, now fitted with Thermotank electric mechanical ventilation units.

Coamings cut to 15" height above deck. Angle rings fitted to take water-tight vent units, bolts on horizontal flanges of landing rings welded in position. Plate blanks, to fit top of coamings, stowed adjacent to ventilators and same marked for position.

POOP DECK:-

Ventilator to Stewards storeroom aft now increased to 12" dia x 2'-6" high above deck, fitted with slide on mushroom tops. Wood plugs and canvas cover supplied for coaming.

G. B. Taylor.
Lloyds Register of Shipping.
Liverpool.

16TH November 1953.

Noted
MR.
9.12.53.

rs

9 DEC 1953



© 2020

Lloyd's Register
Foundation

003391-003400-0066