

REPORT OF SURVEY FOR REPAIRS, &c.

Date of writing Report 22.11.1954 When handed in at Local Office 22.11.1954 Port of LAGOS

No. in Reg. Book 78869 Survey held at LAGOS Date, First Survey 12.11.54 Last Survey 14.11.1954 (No. of Visits)

on the Wood, Iron or Steel

STM. TRAWLER "STRATHALBYN"

Built at Aberdeen By whom Hall, Russell & Co. Ltd When 1929 9

TONNAGE: GROSS 232 Owners Nigerian Shipping & Trading Co. Owners' Address (It not already recorded in Appendix to Register Book)

UNDER DK 212 Managers Port belonging to ABERDEEN

NET 93 Surveyed Afloat or in Dry Dock? Afloat Name of Dock Marine Floating Dry Dock Destined Voyage

Well DBor DBa feet; uE & B feet; f feet Particulars of Classification (which must be inserted precisely as in Register Book & Supplements)

Only alterations in the existing records of tanks should be inserted.

N.B.—All alterations in the existing records should be underlined.

Last Report, No. 725 Port Lyp

Periodical Surveys, when held, must be reported in detail and serially in the terms of the Rules and items remaining to complete the Surveys should be summarised. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors or Chains is reported the particulars should be clearly stated in the space provided on the back of this form. State also the dates and initials of any letters respecting this case.

In damage cases where the Surveyor has not made a special damage report he is required to state whether he offered his services for this purpose and to whom and why they were declined

Was a damage report made by anyone else? if so, by whom?

REPAIRS, OR EXAMINATION AS PER RULE, FOR DOCKING

NOW DONE: Vessel placed in dry dock, shell plating cleaned, scaled, examined and recoated.

Last seen in dry dock 14th November, 1954. Examined internally as far as practicable

the Fish room Bunker Spaces (cleared) engineroom, cabin space aft.

Drillings of shell plates taken see attached sheet.

The decks, casings, hatchways, coamings, vents, closing appliances, windlass, examined.

It was found that several shell plates will be required to be renewed also approximately

1500/2000 corroded shell rivets in D & E strakes (wind & water Line). Decks and masts found

worm eaten. Steel deck plates above boiler thin and wasted. Machinery casing and skylights require

to be part renewed. All closing appliances require to be renewed.

Steering gear rods chains fair leads etc require to be renewed. P.T.O.

SUMMARY OF DAMAGE REPAIRS:—

	Shell Plates.	Frames.	R. Frames.	Floors and Bracket Floors	Beams.	Inner Bottom Plates.	Dk. Plates.	Other Items:—
Renewed ...								
Removed and Fairred or Repaired								
Fairred or Repaired in place ...								

PRESENT CONDITION OF THE parts now surveyed.

Decks (wood) Unsatisfactory Bulkheads

Caulking of Decks Satisfactory Ceiling

Coamings Satisfactory Cement or Asphalt

Beams & Fastenings Good Rudder

Outside Plating Satisfactory Steering gear and its connections

" " In way of sidelights Unsatisfactory Windlass

Frames Satisfactory Have pumps been examined and found efficient?

Reverse Frames Satisfactory Have Sluice Valves been examined and found efficient?

Longitudinals Transverses

Floors Have Watertight Doors been examined and found efficient?

Keelsons Have Ventilators and their Coamings been examined and found efficient?

Stringers Inner Bottom Plating

Have the Tanks been examined internally? No

Have the Tanks been tested? No Air and Sounding Pipes

Doubling Plates under Sounding Pipes

Engine Room Skylights Unsatisfactory

Coal Bunkers, Openings, Covers, &c. Satisfactory

Oil Bunkers

Scuppers

Cargo Hatchways Unsatisfactory

Hatches

Planking

Caulking

Treenails

Breasthooks & Stimson

Transoms, Pointers & Crutches

Timbers of Frame at openings

" " at other places

Stringers, Clamps & Shelves

Salting State if examined

Copper, or Y.M. (State if on Felt.)

When fitted, Month Year

Boats

Masts, Yards, &c. Unsatisfactory

Condition, how ascertained deck

Equipment letter

Anchors, No. of

Cables (State if now ranged)

" length mean diam.

" Rule length size

Chain Locker

Hawsers & Warps

Standing and Running Rigging

Sails

General Observations, Opinion as to Class, Recommendation, &c.:

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:— "to remain as classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 1,38," or "to remain as classed and to have record of survey, 1,38, and the notations of ss No. 1-38."

This vessel is eligible to remain as now classed subject to the vessel being

opened out, and dealt with as necessary according to Rule Requirements for Special Survey D,

also Lloyds Machinery and Screwshaft surveys for Steam Trawlers now

Survey Fee (per Section 23) £ 12 : 12 : 0 Fees applied for, 22.11.1954

Special Damage or Repair Fee (if any) £ : : Received by me, 10

Special attendance £ 7 : 0 : 0

Travelling Expenses (if chargeable) £ 1 : 5 : 0

Second Surveyor's Fee (if any) £ : :

Committee's Minute FRIDAY 17 DEC 1954

Character assigned

Surveyor to Lloyd's Register of Shipping.

Lloyd's Register Foundation

