

Lloyd's Register of Shipping.

Ship's Name **"ANTAR"**

Official No. **168066**

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

Re-opening of tonnage opening.

- (1) The tonnage opening in the shelter deck restored and closed by efficient temporary covers. ✓
- (2) Openings in the tonnage well bulkheads closed as required for full allowance. ✓
- (3) All scuppers led to the hold bilges from the shelter tween decks permanently closed by welded plates. ✓
- (4) The shelter tween deck spaces are drained to the machinery space bilges by two scupper pipes on each side fitted with self closing cocks at their lower ends. ✓
- (5) An overboard scupper 5" in diameter fitted on each side of the tonnage well with a screw down automatic non return valve controlled from the shelter deck having an indicator showing whether the valve is open or shut. ✓
- (6) All hatchways on the second deck fitted with covers, supports, tarpaulins and battening arrangements in accordance with the Rules. ✓
- (7) Two ventilators and two side scuttles on port side aft in way of old gunner's accommodation removed and holes in deck and shell plating closed by welded plates. ✓



F. Brooke Smith
30-1-46

W. Stead
1/2/46

2

