

Port of Portland~~Continuation of Report No.~~dated 17th April, 1941 on the"ANTAR" (For attachment to copy of Freeboard Report )Alterations resulting from arranging accommodation in tween decks aft (port side)

1) 2 brass side scuttles fitted in upper deck sheerstrake (Port aft.)

glasses  $5/8$ " thick and 10" diameter, deadlights permanently attached and can be closed watertight.

2) Washbasin discharges direct through shell in tonnage well. Non-return valve fitted at ship's side.

3) Steel companionway fitted to centre of tonnage hatch. Companionway  $45\frac{1}{2}$ " long x 35" wide x 5'-6" high. Door of steel, hinged, and operated from both sides.

Sill 18" above steel deck.

*Al Hunter**Noted*  
*W.B.*

16 JUN 1941