

Morrison

Particulars of Scuppers and Sanitary Discharge Pipes :—

Particulars of Scuppers and Sanitary Discharge Pipes :-

Crews. etc. under forecastle discharges above forest deck with H.R.V. on shell ✓
Officers .. on R.Q.D. discharges about 6'0" below deck with H.R.V. on shell ✓
Scupper from weather deck discharge above deck ✓

Particulars of Side Scuttles:—

In precast about 2.0' below fut. deck rim bridge have strong frames & are filled with hinged dead lights -

Particulars of Guard Rails :—

On presettle 5'0 high, 2 roots, stanchions about 4'6" apart -
 Stiebs bulwarks on R. & O. in well & on Bridge strong & efficient. ✓

Particulars of Gangways, Lifelines, etc. :—

nona petra -

Ship's Name MORION. Official Number 143608.
Type Raised Quarter Deck, Bridge and Forecastle.

PARTICULARS OF SUPERSTRUCTURES.

Particulars of fiddley, funnel and ventilator coamings:—
Ventilators strong & efficient. — Engine, flylight head with head flaps, glass frames protected with brass rods. — Coatings closed with hinged steel covers. —

Particulars of Flush Bunker Scuttles:—

home - ✓

Particulars of Companionways :



Particulars of Companionways:— *The Bridge deck, stair to cabin, covered by strong steel house -*
1/2" Deck door 5'4" x 2'0" with hinges & lock operated from both sides - sill 1" - ✓
1" on foreboard deck full height of forecabin, steel 1/4" thick 3'6" x 2'6" covering stair to
cruiser's quarters - ~~Deck~~ ^{Seak} door 2'0" x 5'0" x 1 1/2" with lock & hinges operated from both sides -

Particulars of Ventilators in exposed positions on freeboard and superstructure decks:—

Particulars of Ventilators in exposed positions on freeboard and superstructure decks :—
one 10' Vent forward & one aft in fore well, to hold - Coaming 36" x 40" ✓ Ventilator according to rule
" 8' " on forecabin to crew quarter - Coaming 36" x 40" ✓ No wood plug or cover
Satisfactory means of closing provided.

Particulars of Air Pipes in exposed positions on freeboard, raised quarter, or superstructure decks :—

Particulars of Air Pipes in exposed positions on freeboard, raised quarter, or superstructure decks:—

One to fore peak under open foreside, top 14" above deck - ~~cover required~~ → 
One on R.Q.D. aft to after peak, top 9" above deck, ~~flange cover required~~ → 

Satisfactory means of closing provided.

Particulars of Gangway Cargo and Coaling Ports :—

None -

Poop Bulkhead	...	✓	
Raised Quarter Deck Bulkhead	...	✓	
Bridge, After Bulkhead	...	✓	
Bridge, Forward Bulkhead	...	✓	
Forecastle Bulkhead	...	✓	
Exposed Machinery Casings on Deck	...	✓	
Exposed Machinery Casings on Superstructure Decks	...	✓	
Machinery Casings within Superstructure, & fitted with Class I Closing Appliances	...	✓	
Deckhouses on Flush Deck Ships	...	✓	

Circular light about 9' dia strong frames no doublelight - ✓

2 steel doors to E. room with hinges & locks operated from both sides. ✓
both sides

4 " " " " Stakehold " " " both operated from one side.

ID © 2020