

5 JUL 1949

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name *GLENBRIDE*

Official No. 143608

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

in

Accommodation has been removed from under upper deck forward to under the forecastle deck.

The forecastle has been extended 15' & an efficient bulkhead erected of 7/16" plating with stiffeners 2 1/2" x 2 1/2" x 26" spaced 30" max. brackets fitted top & bottom 15" on forecastle apparently plated over.

Doors 4' 8" x 2' side 15" hard wood doors 2" thick fitted to the forecastle accommodation, W.C. & wash Room & doors to poop Room mess Room of steel 32 are doors operated from both sides.

Forecastle wood deck renewed where necessary.

Two ventilators fitted 8" Dia 3' high 4" diam go

3 Goose necks fitted

Side scuttles fitted with dead weights - efficiently & strongly constructed

L. H. Wiggall

G.H.W.

11.7.49



© 2020

Lloyd's Register
Foundation

003421-003428-0227