

# Lloyd's Register of Shipping.

Ship's Name "EMPIRE TWED".

Official No. 154.532.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in

RESTORING OF THE TONNAGE OPENING.AS PER LONDON LETTER OF THE 30th OCTOBER, 1945.

TONNAGE OPENING. in the Shelter Deck now restored and fitted with efficient wood covers, secured on underside by rope lashings.

TONNAGE OPENINGS. in the Tonnage well bulkheads now closed by 3" boards fitted in channels as originally.

BULKHEADS ON NO.65 FRAME. starboard side, and 67 frame, port side E.W. plates fitted over openings now removed and 3" boards fitted in channels as originally.

BULKHEADS ON NOS. 36 and 133 FRAMES. have now openings 49" x 36" wide with 21" coaming on p & s sides and temporary bated plates fitted over openings.

SCUPPER PIPES led to Hold Bilges now cloased by E.W. Plates and the Tween Decks drained by scupper pipes to the machinery space bilges with self-closing cocks at their lower ends. Slets are cut in tween deck bulkheads at sides for the drainage of water to the Machinery space bilges.

TONNAGE WELL SCREW -DOWN NON-RETURN VALVES. controlled from the Shelter Deck on p & s sides, originally fitted, now overhauled and made good.

LOAD LINE SURVEY now carried out, markings verified and re-cut.

New Certificate and copy issued.

*A. G. Marshall,*

SURVEYOR TO LLOYD'S REGISTER.

LIVERPOOL.

15th December, 1945.