

for Mr. Ward, Wokingham

s.s. "EMPIRE FOAM"

Messrs. Swan, Hunter's No. 1694

Rule Dimensions:- 425' x 56' x ^{36.8%} 36.75' to upper deck
27.75' to 2nd deck

Class:- 100A1 with freeboard

This vessel is one of the standard Lithgow "Y" type Emergency vessels, and the scantlings have been made suitable for a draught of 18" in excess of that corresponding to the freeboard which can be assigned as a C.S.S. vessel.

The watertight bulkheads have been extended to the upper deck. (*Scantlings in holds not sufficient for H to weather deck*)

A reduced length of cable has been accepted, and the 3rd bower anchor dispensed with.

A proposal to fit the three strakes ^{from} ~~to~~ the centre ~~line~~ ^{strake} of the tank top plating of .45 in thickness and the strake next to the margin plate .42 in thickness, to suit American plates, was approved.

There are no other points in the correspondence affecting the first entry.

26th June, 1941.



Lloyd's Register
Foundation

003434-003443-0037