

GLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping
Signal Letters (if any) ----- L.H.C.K. -----

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
162,577.		Guinness.		61 in 1931 London.	
No., Date, and Port of Previous Registry (if any). -----					
Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Ship Single Screw.	Troon	1931	Ailsa Shipbuilding Co., Ltd., Troon.	
Number of Decks ... One		Length from fore part of stem, under the bowsprit, to the		Feet.	Tenths.
Number of Masts ... Two		aft side of the head of the stern post 		211	8
Rigged ... Fore & Aft Schooner		Length at quarter of depth from top of weather deck at			
Stern Cruiser		side amidships to bottom of keel 		208	1
Build Clencher		Main breadth to outside of planking 		34	4.5
Galleries -----		Depth in hold from tonnage deck to ceiling at midships ...		16	6.5
Head -----		Depth in hold from upper deck to ceiling at midships, in the			
Framework and description of		case of three decks and upwards 		--	--
vessel Steel Cargo		Depth from top of beam amidships to top of keel 		19	7
Number of Bulkheads ... Four		Depth from top of deck at side amidships to bottom of keel		19	4.2
Number of water ballast tanks,		Round of beam 		--	7
and their capacity in tons ... Four-277 tons.		Length of engine room, if any 		42	--

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 2127 Tons. Ditto per inch immersion at same depth ... 14.2 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set. Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B.H.P. I. H. P. Speed of Ship.
One	Triple expansion Direct Acting Vertical.	Engines. British	Engines. 1931	Engines. Ailsa Shipbuilding Co., Ltd., Troon.	Three 16½" 27½" 33"	-----	104.82
No. of Shafts.	Particulars of Boilers. Cylindrical Multitubular	Boilers. British	Boilers. 1931	Boilers. J.G. Kincaid & Co. Ltd., Greenock.	46"		1010
One	Description. Two						11 Knots.
	Number. Steel						
	Iron or Steel. 200 lbs.						
	Loaded Pressure. 200 lbs.						

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	958.64	On account of space required for propelling power	437.34
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	71.99
Turret or Trunk ...	37.65	These spaces are the following, viz.:— Forecastle, Side Houses & Round Houses (Number of Seamen or Apprentices for whom accommodation is certified.....15.....).	
Forecastle...			
Bridge space ...			
Peep or Break Crown ...	2.97		
Side Houses ...	30.53		
Deck Houses ...	30.23		
Chart House ...	4.30		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	34.16	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways ...	52.08		
Gross Tonnage ...	1150.56	* Cubic Metres Masters Accommodation 16.54	
Deductions, as per Contra ...	594.46	Chart Space 4.30	
Register Tonnage ...	556.10	Boatswain's Store 11.51	
		Steering Gear Spaces 21.56	
		Water Ballast " 31.22	
		Total ...	594.46

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 222.84 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 34.16 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Under navigation bridge abreast R.H.No.2.Port & Starboard L.12.0 ft.L.12.0 ft - 7.44 tons	
" boat deck aft abreast S.H.'s Port L.32.2 ft.L.6.5 ft -12.89 tons	
do do Starboard L.32.2 ft.L.2.4 ft)-13.92 tons.	
	L.6.0 ft)

Name of Master

Certificate of { Service No.
Competency No.

No. of Owners



Name, Residence, and Description of Managing Owner if there are more owners than one.

Arthur Guinness Son & Co., Limited
St. James's Gate Brewery,
Dublin.

Shares:- Sixty-four.

William Edward Francis
Manning of same address
-Manager-.

Dated 28th April, 1931.



Lloyd's Register
Foundation