

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name GUINNESSOfficial No. 162577

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

HINGED STEEL WEATHERTIGHT DOORS IN BRIDGE FRONT (CLASS-1.) OPERATED FROM BOTH SIDES. 5' x 2' OPENING. 18" SILL. ✓

COMPANIONS ON BOAT DECK. A.B.C. OF STEEL WITH HINGED 2" WOOD DOORS. OPERATED FROM BOTH SIDES. 5' x 2' OPENING. 18" SILL. ✓

ACCESS TO HOLD. 'D' OF STEEL WITH HINGED STEEL DOOR OPERATED FROM BOTH SIDES 4' x 2' OPENING. 24" SILL. (WITHIN FEEL SPACE) AND INSULATED WOOD PLUG HATCH. ✓

VENTILATORS ON BOAT DECK. 17- 5" DIA GOOSENECK PIPES 27" HIGH. ✓
2- 8" " x 3/8" - 30" HIGH. ✓
2- 9" " x 7/8" - 30" " ✓
2- 12" " x 7/8" - 30" " ✓

VENTILATORS PROVIDED WITH WOOD PLUGS. & CANVAS COVERS. ✓

AIR PIPES ON BOAT DECK. 4- 2" DIA. x 15" HIGH. WOOD PLUG FITTED. ✓
2- 4" " x 15" " " " " ✓

SCOPPERS & DISCHARGES. FROM AFT ACCOMMODATION. LED OVERBOARD BELOW UPPER DECK WITH 2 BRASS. N.R. VALVES ONE AT SHIPS SIDE & THE UPPER ALWAYS ACCESSIBLE. ✓

LIFELINES PROVIDED FROM BRIDGE FRONT TO FEEL FRONT. ✓

H. Berry
28/12/53.

Noted
J. H. H.
1/2/54.