

Lloyd's Register of Shipping.

Ship's Name "MAGDALENE VINNEN" Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1935.

HATCHES. Hatch on forecastle 1-10 $\frac{1}{2}$ " square. Coaming 24" high x $\frac{3}{8}$ " thick. 5/16" hinged steel cover rubber jointed secured by 6 toggles.

Hatch in forecastle 4' x 3' coaming 9" B.A. 2 $\frac{1}{2}$ " wood covers laid athwartships with 2 $\frac{1}{2}$ " bearing. Cleats and battens to Rule. 1 tarpaulin.

Hatch on upper deck port side 2'-0" x 2'-9". Coaming extends to 24" above forecastle deck. Up to forecastle deck level $\frac{1}{4}$ " thick on 3 sides and fore side formed by forecastle front. Above forecastle level coaming $\frac{3}{8}$ " thick. 5/16" Hinged steel cover rubber jointed secured by 6 toggles. There are now no stiffeners on No.3 bridge deck hatch.

Hatch on bridge port and starboard abreast No.3 main hatch 3'-9" x 3'-6" coaming 18" high x 5/16" thick. $\frac{1}{2}$ " hinged steel cover rubber jointed. 2 hinges at fore end and 2 toggles at after end.

Original side bunker hatches on bridge now shortened to 10'-1".

Original poop hatch dispensed with.

Hatch on poop 4'-0" x 4'-0" coaming 26" high x $\frac{1}{2}$ " thick. Cleats 18" apart. 2 $\frac{1}{2}$ " wood covers with 2" bearing. 2 tarpaulins.

Hatch on poop 2'-0" x 2'-9". Coamings 24" high x $\frac{5}{8}$ " thick 5/16" hinged steel cover rubber jointed secured by 6 toggles.

Hatch on poop 2'-0" x 2'-0" Coaming 24" high x $\frac{3}{8}$ " thick. 5/16" hinged steel cover rubber jointed secured by 6 toggles.

Hatch in poop to tunnel escape 2' x 2' Coaming 3 $\frac{1}{2}$ " high x 5/16" thick. $\frac{1}{8}$ " Hinged steel cover secured by 1 fastener.

Original hatch in poop dispensed with.

VENTILATORS. All original ventilators on Forecastle deck dispensed with.

On Forecastle 9 gooseneck vents. 10" x 3". 24" high to lip with hinged steel cover secured by a toggle.

On Upper deck s.s. abaft forecastle front 1 ventilator 6" diameter. Coaming 3'-0" high x 3/16" thick. Plug and cover provided.

All original ventilators on Poop deck dispensed with.

On poop deck 2 cowl vents. 7" diameter. Coamings 1'-10" high x $\frac{1}{2}$ " thick.


Plugs and covers provided. One vent. 10" diameter, coaming 2'-6" high x 5/16" thick and one @ 7" diameter, 2'-6" high x 5/16" thick each having mushroom top, eight gooseneck vents. 10" x 3", 21" high to lip and having hinged steel cover secured by toggle.

AIRPIPES. On forecastle under breast hook 1 @ 3" diameter 6" high, port side 1 @ 3" dia. 2'-9" high and s.s. 1 @ 3 $\frac{1}{2}$ " dia. 1'-2" high.

SCUPPERS & SANITARY DISCHARGES.

From lavatories in poop bridge and forecastle discharge overboard below upper deck each through a stormvalve.

SIDESCUTTLES. In poop and bridge with efficient hinged deadlights.



© 2020

Lloyd's Register
Foundation

FREELING PORTS. 2 additional each side of forward well 3'-8" x 1'-3", 22" above deck, 41'-0" and 75'-0" from bridge front. Each with 1 rail.

CLOSING APPLIANCES.

Poop bulkhead. Original opening dispensed with.

Opening at centre 5' x 2'-6" with 18" sill. Hinged steel door rubber jointed.

Secured by 2 toggles and spring lock. Manipulated both sides.

3 openings s.s. each 5'-0" x 1'-10" with 16" sills. Hinged steel doors rubber jointed and each secured by 1 toggle manipulated from both sides.

BRIDGE AFTER BULKHEADS. Original openings reduced to 4'-8" x 2'-0" with 24" sills, closed by hinged steel doors rubber jointed and each secured by one fastener manipulated from both sides.

BRIDGE FORWARD BULKHEAD. As before.

FORECASTLE BULKHEAD. Original openings dispensed with.

2 openings each 4'-8" x 2'-0" with 18" sill, closed by hinged steel door rubber jointed and secured by 1 toggle manipulated from both sides.

MACHINERY CASINGS IN BRIDGE. One opening starboard side of fiddley 5'-6" x 1'-9" with 9" sill. Hinged steel door manipulated from both sides.

Items not mentioned in foregoing.

3 steel skylights on bridge deck starboard side and 1 port side. No flaps. Fixed lights with portable steel storm covers. 2 bullseye decklights in poop deck of substantial construction.

J. W. Thoms



© 2020

Lloyd's Register
Foundation