

## Lloyd's Register of Shipping.


Ship's Name M.S. "ETTRICKBANK"

Official No. 165920

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
 whilst building.

The small hatch (40" x 36") on shelter deck aft to steering gear compartment has now been removed, and a new hatch 31½" x 41½" fitted against port after corner of deck house, coaming 19" (above wood deck) x .40, 3" covers fitted fore & aft on 2½" test bars, cleats spaced 16" maximum, two tarpaulins.

E. J. Brimblecombe.

S.E.B.  
6.1.39.