

Lloyd's Register of Shipping.

110 JUL 1947

Ship's Name S.S. "~~HARMAC CHEMAINUS~~" *BIMBAY* Official No. 175363

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in February, 1944

ALTERATIONS:-

Existing Engineers' deckhouse extended forward on port and starboard sides and one additional cast steel S.D. non-return discharge valve fitted below second deck on starboard side in way operated from above the freeboard deck and provided with means for indicating whether "open" or "closed."

2 - 12" cowl ventilators, which had been installed to butcher's shop and dry stores in 'tween deck port and starboard sides since ship was surveyed for assignment of Load Lines in February, 1944, now permanently removed and openings in decks efficiently closed with welded spigot plates.


Bulkheads on port and starboard sides of No. 5 'tween deck removed and new watertight bulkheads constructed at frame 22 on port and starboard sides. 3 side scuttles in way and 2 storm valves below level of second deck now permanently removed and apertures closed with welded spigot plates.

Outboard sections of No.5 bulkhead moved aft for two frame spaces in way of steering gear compartment to provide additional accommodation, and one storm valve above level of second deck in way permanently removed and shell opening efficiently closed. Steel companionway to after accommodation and hinged steel watertight door to steering gear compartment removed and openings in casing side and upper deck permanently closed with welded plates.

Hose tested in way of removals and found satisfactory.

D. J. Archibald

SURVEYOR TO LLOYD'S REGISTER

hoped 

10 JUL 1947

Vancouver, B. C.

2nd June, 1947.

No copy of this report has been placed on board the ship being of Canadian Registry.



© 2020

Lloyd's Register Foundation