

## Lloyd's Register of Shipping.

Ship's Name *S/S "CORINTHIAN"*Official No. *166246*Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in *1938*.

An additional coal hatch cut during Admiralty Service  
in bunker 'tween decks alongside bunker casing port  
& starboard has been retained.

Hatches *7'6" x 3'0"* with *9" B.A. Coaming*, *2½ net bars* and  
cleats & battening arrangements to rule requirements.

Satisfactory companionways have been embodied in  
the after deckhouse at the port & starboard sides  
forward leading to the accommodation in 'tween  
decks aft.

*2" solid hardwood doors, hinged, 5'0" x 2'0"* operated  
from both sides. Sills *18"*.

A steel *H.T. door, hinged*, has been fitted at the after  
end of the after deckhouse to the companion leading  
to crew's quarters in 'tween decks in lieu of wood  
door previously fitted.

*W.J.C.*