


25 APR 1942



Steamer "RUNMARÖ".

7601.

Stockholm, on 23.12.31 - 29.3.32.

Crew's quarters shifted from forecastle space to poop space as per attached plan. Openings in poop bulkhead closed. Coaming, plating, stiffeners, spacing and end attachments of stiffeners same as before.

Access to Crew's quarters through deck house erected on poop deck.

Deck house also containing Crew's wash rooms and W.C.

Dimensions of deck house:-

Length	2.90 metres	}	20.58 m ³
Breadth	3.30 "		
Height	2.15 "		

Height of sills 457 mm.

Dimensions of poop enclosed:- *Tonnage length*

Length	9.54 metres	}	168.17 m ³
Height	2.03 "		

Closing appliances:-Poop bulkhead:-

No openings. ✓

Bridge after bulkhead:-

Portable plates with hook bolts, not passing through bulkhead, spaced 12" apart capable of being manipulated from outside only. ✓

Bridge forward bulkhead:-

Hinged steel doors p. & s. ✓

Forecastle bulkhead:-

3" wood boards in riveted channels for full height of opening. Opening in centre line. Breadth of same 1.10 metres. *Steel hinged door to lamp room fwd.*

The vessel has been re-measured as follows:-

British gross tonnage	2831.39
" net "	1642.95
Under deck	2553.09
Swedish gross tonnage	2835.18
" net "	2065.70

W. A. Pilow

Fee:- Sw.Kr. 80:00



© 2020

Lloyd's Register
Foundation

003474-003478-0029