

DIMENSIONS.

LENGTH AS PER RULE	104'-4 1/4"	59.25 M.
BREADTH MOULDED	32'-0 5/8"	10.00 M.
DEPTH MOULDED TO MAINDECK	12'-5 5/8"	3.80 M.
DEPTH MOULDED TO SHELTERDECK	19'-6 1/4"	5.95 M.
HEIGHT OF DECKSHOUSE ON SH/DK	6'-10 3/4"	2.10 M.
HEIGHT OF DECKSHOUSE ON BOAT/DK	6'-10 3/4"	2.10 M.
DRAUGHT ON SUMMER FREEBOARD	ABOUT	3.75 M.

The scantlings are suitable for a summer moulded draught of about 3.75 METRES.  
The minimum freeboard will, however, be determined on completion of the ship by the Regulations of the Load Line Convention.

EQUIPMENT NUMERAL:

$L \times (3+d) + 0.85 \times L \times (3-d)$		= 925
FORECASTLE	$0.85 \times 6.0 \times 2.0$	= 10
DECKSHOUSE ON SHELTERDECK	$0.75 \times 11.9 \times 2.10$	= 19
DECKSHOUSE ON BOATDECK	$0.85 \times 5.0 \times 2.10$	= 9
---	$0.75 \times 2.4 \times 2.10$	= 4
WHEELHOUSE	$0.75 \times 5.8 \times 2.10$	= 9
	<b>TOTAL 976</b>	
	<b>Letter = L</b>	

FINAL NUMERICAL TO BE DETERMINED ON COMPLETION OF SHIP.

EQUIPMENT.

3 BOW ANCHORS STOCKLESS WEIGHT  $\times 3 \times 1030$  KG  
0.85 M. 35% # WROUGHT IRON STUD CHAIN CABLES  
165 M. 7/8"  $\phi$  6 x 12 FLEXIBLE STEEL WIRE ROPE BRASSING STEEL 10 PER RULE  
3.165 M. 1 1/4"  $\phi$  4 x 12 FLEXIBLE STEEL WIRE ROPE

CLASS.  
LLOYD'S REGISTER + 100 AI  
"STRENGTHENED FOR NAVIGATION IN ICE"  
PART. ELECTRICALLY WELDED.  
LONGITUDINAL FRAMING AT BOTTOM.

CRANES, STEERING GEAR, WINDLASS, DAVITS  
ETC. TO BE SUPPORTED TO SURVEYOR'S SATISFACTION.

The flesh part of the oil fuel to be above 65.5°C and the remaining requirements of Section 20 of the Rules 19.55 to be complied with so far as they are applicable.

FRAME SPAC: 600%.

The remaining requirements of section 10 of the rules 19.55 to be complied with so far as they are applicable.

1.

MS  
22.01.20

10 JAN. 1957

SÖLVESTRÖMS VARVS FÖRETAG A. B.  
SÖLVESTRÖM

M/S 49-52

MIDSHIP - SECTION.

© 2020

PLAN	SECTION	SCALE	BY	CHKD
21.01	21.01	1:25	49-020	49-020



Malmö.

Sölvesborgs Varvs- & Rederi A.-B.

M/S 49 "Ofelia"


Midship Section.

(Malmö Trunk. Rpt. No. 3724  
of the 17/2-1957)

5201 7/11 11




RECORDS DEPT.,  
LONDON.



003487-003494-0279

© 2020



Lloyd's Register  
Foundation