

Received by Chief Ship Surveyor  
GB

Received from Chief Ship Surveyor

110 JUL 1950

VESSEL'S NAME 'B A L I' REPORT Ham. No. 971

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/52.)

The Periodical Special Survey (C), due 1.50 was commenced Osl. 1.50 and advanced Nwc. 2.50 & 3.50.

ACTION is DEFERRED for completion of Special Survey.

The indented bottom and side shell plating, etc. (p & s) required to be dealt with by the next Special Survey.

The HAMBURG Surveyors report (5.50), the vessel placed in dry dock and the Special Survey completed.

It was not considered necessary to drill the shell plating.

In consequence of various damages (4), repairs have been effected to indented keel, bottom and side shell plating, etc. (p & s), including those plates as above.

The vessel has now been converted for the burning of oil fuel in accordance with approved plans, and to Rule requirements.

An additional W.T. bulkhead erected on frame 65 and the original cross bunker space converted into two deep tanks with settling tanks in 'tween decks.

In connection with this conversion, the inner bottom plating in the original cross bunker space has been renewed with the exception of the centre strake.


IT IS SUBMITTED the vessel's class be amended to 100A "With freeboard" "Fitted for oil fuel 5.50, F.P. above 150°F" with record of docking survey 5.50, and to have the Notation of 'ss. Ham. 5.50' assigned as recommended, without special conditions.

100A "With Freeboard" "Fitted for oil fuel 5.50, F.P. above 150°F" 5.50 Ham. Without.  
ss. Ham. 5.50

AMEND R.B.

FROM :- 5BH Coll ~~to~~ to Sh dk, 4 to 2nd dk  
6BH Coll ~~to~~ to Sh dk, 5 to 2nd dk

CLIP M sent records 6/7/50.



2020  
Lloyd's Register  
Foundation