

Lloyd's Register of Shipping.

51 DEC 1941

Ship's Name "Plover"

Official No. 164627.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Accommodation for defence personnel fitted at Aft. End of Forecastle Tween Decks.

Particulars of Companionway:-

Entrance to Gunners' Accommodation, Opening 45" x 25" (24" oill.)

Hardwood door - can be operated from both sides.

Particulars of Ventilators:-

One - 6" dia cowp vent - 30 x 36" above forecastle deck. (wood plugs + canvas cover fitted)

Three - 4" dia S.H. do. - 36" above forecastle deck. (wood plugs fitted.)

Particulars of Side Scuttles:-

4 - 10" dia sidelights, with metal deadlights, through forecastle front.

Particulars of Scuppers and Sanitary Discharge Pipes:-

One - 2" dia washbasin discharge, led overboard, S.V. at shell, above freeboard dk.

Two - 1 1/2" do. flap scuppers (P.S.) through forecastle front.

Noted L.W.B.

Robert Wood

Surveyor to Lloyd's Register of Shipping

25/11/41.

(Leith)

2 DEC 1941



© 2020

Lloyd's Register
Foundation

003503-003512-0258