

Ship's name CALGARIA

Port LIV.

No. 160844.

Pass is subject to

^{at}
124.12.62 + Last survey date 29.12.62.

Starboard propeller and fastenings being specially examined at the next dry-docking.

Docking, Port Screwshaft examined.

Wear down! - P. before newwading '180"
after " (close fit)
S. '103"

SAH itur Starboard propeller examined and a crack 8 inches long found running longitudinally from tip of one blade, and 3 inches missing from tips of two adjacent blades.
End of crack drilled at this time and the surveyor considers the propeller efficient meantime, but recommends the Starboard propeller being specially examined and dealt with as necessary at the next dry-docking.

It is submitted that this vessel is eligible to remain as CLASSED.

with fresh record of:-
TS.(CL) P. 12.62 now, subject as now amended and recommended.

00513-003524-0155