

9 - MAY 1956

Rpt. C. 11 (Contd.)

Index No. 17200  
(For London Office use)

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

40297

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name *Ocean Layer* Official No. *181837*

Port of Registry *London*

This ship has been under survey at *Manchester*  
on *3rd May 1956* 195 and the following alterations to the conditions of

assignment of loadlines have now been effected/found:-

*Addition (To Lead Cable through Bridge Deck direct to No 2 Cable Tank)*  
An 18" diam access cut in Bridge Deck in the frame space forward of the  
Captains Accommodation approximately 18" off Centre Line to port. A double  
welded on Deck 3'-0" long and for full width of frame space in way, and a coaming  
9" high of Strong Steel construction fitted through aperture with bell-mouth  
bottom below beams. The Coaming closed with a bolted plate on top on a  
3' x 3" Angle Ring with watertight insertion between Ring and Coam.

AR  
15-5-56

*Jack Stanters*  
*Surveyor to Lloyd's Register of Shipping*  
*Manchester*  
*4th May 1956*

A copy of this Report has been placed on board.

2m.6.58. T.