

COPY

Ship's name

"AKTI"

Port

IST

No. 5271

Class is subject to Nil

Last survey date 13.12.62

CSM advanced.

Damage repairs effected to the scavenge blowers, all damaged gear teeth now filed to true profile, two scavenge blower shaft bearings and both intermediate gear wheel bearings remetalled and temporary repairs made to the blower transmitting springs by fitting suitable packing pieces and on completion ahead and astern manoeuvring effected without difficulty and full power was developed before vessel continued on voyage.

Whilst repair is considered satisfactory meantime surveyor recommends that the scavenge blower driving springs be renewed by the end of February 1963 (2 months limit).

IT IS SUBMITTED that this vessel is eligible to remain as classed subject as now recommended.

For CSM see form 7E.



© 2021

10.1.63.  
Lloyd's Register  
Foundation

003567-003571-0045