

54 MAY 1937

G.R. 130.
CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.
Signal Letters (if any) G.Z.Q.X.

Official Number.	Name of Ship.		No., Date, and Port of Registry.		
165657	LOCH OSKAIG.		34/1937	Hull.	
No., Date, and Port of previous Registry (if any).					
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Ship Single Screw	South Bank-on-Tees	1937	Smith's Dock Company Limited South Bank-on-Tees.	
Number of Decks	One	Length from fore part of stem, to the aft side of the head of the stern post		Feet.	Tenths.
Number of Masts	Two			173	6.5
Rigged	Ketch	Main breadth to outside of plank		28	6.0
Stem	Straight	Depth in hold from tonnage deck to ceiling amidships		15	0.5
Stern	Cruiser	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards		-	-
Build	Clincher	Depth from top of deck at side amidships to bottom of keel		16	6.2
Framework and description of vessel	Steel Fishing	Round of beam		-	6.7
Number of Bulkheads	Four W.T. One Non-W.T.	Length of engine room, if any		36	7.5

Particulars of propelling Engines, etc., (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Estimated Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Vertical Triple Expansion Surface Condensing	Engines.	Engines.	Engines.	Three			99.0
		and	and	Smith's Dock Co. Ltd., South Bank-on-Tees.	14 1/2"	27"	-	925
No. of Shafts.	Particulars of Boilers.							About 12 1/2 Knots.
One	Single Ended Multitubular	Boilers.	Boilers.	Boilers.	24"			
	Number One	British	1937	Richardsons Westgarth & Co. Ltd., Hartlepool.	41 1/2"			
	Iron or Steel Steel							
	Loaded Pressure 225 lbs. sq. in.							

Number of water ballast tanks, and their capacity in tons:— Two - 20 tons total.

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		467.21	On account of space required for propelling power		241.59
Space or spaces between Decks			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew		64.40
Turret or Trunk			These spaces are the following, viz. :—		
Forecastle	House in.	3.91	Below Deck, forward & aft.		
Bridge space			(Number of seamen or apprentices for whom accommodation is certified. 23)		
Peep or Break		18.37	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—		
Side Houses			Masters Accommodation		5.45
Deck Houses	Round Houses.	31.10	Chart Space		5.44
Chart House			Wireless Space		3.86
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		13.88	Boatswain's Store		10.00
Excess of Hatchways			Water Ballast Spaces		6.04
			Total		30.79
Gross Tonnage		534.47	Cubic Metres.		
Deductions, as per contra		336.78			
Register Tonnage		197.69			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 124.17 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 25.82 tons.


NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle L.24.5' - 29.71 tons.

Name of Master	Certificate of	Service No.	No.
	Competency	No.	
No. of Owners	Name, Residence, and Description of Managing Owner if there are more owners than one.		
	The Caledonian Fishing Company Limited, 164, Market Street, Aberdeen.		
	Harry Wight, St. Andrews Dock, Hull - Manager.		
	Sixtyfour (64) Shares.		
Dated 26th April, 1937.			

*940. Wt.17581/020. 500. 8/36. W.y.P.C. 613.
1770. Wt.28798/045. 1000. 12/36.

GENERAL REMARKS—(The Surveyor should state the Number of Report and Name of any Sister Vessel. Plans showing Vessel as built should be forwarded and a List of the Plans should be embodied.)



Mr. Godkin

Rpt. 4



Date of visit
No. in Reg. Book
Built at
Engines
Boilers
Registered
Nom. Horse Power
Remarks
TY

SP
Partic
Case
We
Nu
of'
PAR
partic
No.
Doubt
Doubt
Doubt
Doubt
Doubt
Order
Dat