

Lloyd's Register of Shipping.

(Report on Machinery, No. _____ Port _____)

No. 1130 ENGINE FORGINGS OR CASTINGS.


I have to report that the ~~Forgings or Castings~~, as herein described, manufactured by Blackell, Shuller & Co. of Greenwich works for the Engines No. 381 being constructed by Smith Dowl & Co. of South Park or Yew for the Ship No. _____, being built by _____ of _____ have been inspected by me as set forth below, and found to be, so far as can be seen, sound and free from defects. These have been despatched to South Park

The words FORGINGS or CASTINGS should be struck out as may be required.

Mark on Forgings or Castings.

Lloyd's
No. 1130
④ 4430

1 Junction piece for
main steam pipes



	CRANK SHAFT.	THRUST SHAFT.	INTERMEDIATE SHAFT.	TUBE SHAFT.
	FLYWHEEL SHAFT.			SCREW SHAFT.
Material* ...	S. M. Acid Open Hearth Steel			
How made ...	Cast			
If Annealed...	Y			
Dimensions, Forgings	2.1.26			
Weight, Castings	— single 005 lbs			
Progress on Inspection				
Tests on Standard Test Pieces.				
Tensile Test— Tons per square inch	28.4			
Extension per cent	26			
Cold Bending Test— Angle before fracture	180° H.F.			
Dates when Inspected	4. 4. 30			

PARTICULARS OF OTHER TESTS APPLIED TO CASTINGS:—

H. V. Survey This casting, after machining, tested by hydraulic pressure to 6000 lbs. per sq. inch and found

Satisfactory

Fee (if any chargeable) £ 10/6

To be paid at _____

16.4.30

* If of wrought iron, state whether piled bars or scrap. If of steel, state whether made by the Open Hearth process.

