

COPY.

142

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C. 3.

18th February, 1936.

Dear Sir,

E.

With reference to your letter of the 7th instant, with enclosures advised therein, respecting shafting proposed for Messrs. Deutsche Werft's Yard No.181, I have to inform you that, with 2 SCSA oil engines for main propelling purposes, having 8 cylinders, diameter of cylinders 520 mm., stroke 900 mm., span of bearings 680 mm., revolutions per minute 170, maximum pressure in cylinders 45 Kgs. per square cm., M.I.P. 5.5 Kgs. per square cm., and B.H.P. 2600, the following size of shafting will be approved, viz:- Crank 350 mm.

The plan showing details of the crank shaft will also be approved, and one copy is being returned to you under separate cover.

I am, Dear Sir,

Yours faithfully,

Secretary.

V.F.J. Sdrowok, Esq.,
AUGSBURG.



© 2020

Lloyd's Register
Foundation

003599-003604-0317