

No. of Donkey Boilers
Steam Pressure—
in Main Boilers 213

Managers

Owners Address
(If not already recorded in Appendix to Register Book)
Port PANAMA

4 E

Chief Engineer Surveyor

Received from Chief Engineer Surveyor

SHIP NAME "PAN OCEAN" REPORT Alx. No. 3994

The remarks of the Chief Engineer Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Survey ~~REPAIRS TO ENGINES AND BOILERS DUE TO DAMAGE THROUGH~~

The class is subject to the port boiler port and starboard furnaces, centre boiler port furnace and the starboard boiler port furnace being specially examined before the end of 2.50.

BS due 12.49 held now, and the screwshaft examined.

Wear and tear repairs

Electric welding effected to combustion chamber plating and some screwed stays renewed.

S.R.L. All boiler furnaces have been specially examined and the Surveyor reports they continue efficient. It is recommended, however, that port boiler port and starboard furnaces, centre boiler port furnace and starboard boiler port furnace be specially examined at next Boiler Survey.

Alterations

The vessel has been converted from coal to oil burning in accordance with the Rules. The extended spindles to the deep tank suction, oil fuel unit and steam smothering stop valves have yet to be installed.

IT IS SUBMITTED that this vessel is eligible for the record BS 4.50, S 3.50 now, and notation of "Fitted for oil fuel 4.50, F.P. above 150°F" when extended spindles have been fitted to deep tank suction and to steam stop valves of oil fuel unit and steam smothering installation.

Subject to port boiler port and starboard furnaces, centre boiler port furnace and starboard boiler port furnace being specially examined at next Boiler Survey.



© 2020
W.S.S.

31. 5. 50.

Lloyd's Register
Foundation

003599-003604-0395

Survey Fee (per Section 29) LE41.500

Fees applied for
21/4/19 50.

and P furnace in starboard boiler