

Lloyd's Register of Shipping.

Ship's Name S.S. "EMPIRE INDUS "Official No. 168359

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in compliance with instructions received the following alterations have been carried out.

- (1) The height of the Companionway sill has been raised to 24" ✓
- (2) The escape skylight coaming on poop raised to 24". ✓
- (3) The fiddley door sills raised to 24".

- (4) Arrangements have been made to restore the scuppers now draining the exempted poop and bridge spaces to the bilges, to overboard scuppers with storm valves, this will be attended to on vessel return from present voyage.

The following Freeboards have been assigned and checked on the ship sides.

Freeboard Amidships from tip of deck line (steel deck)

		From Centre of Disc.
Tropical Fresh water	2 ft. 10½ ins.	13 ins. above.
Fresh water	3 " 4¾ "	6¾ " "
Tropical	3 " 5¼ "	6¼ " "
Summer	3 " 11½ "	
Winter	4 " 5¾ "	6¼ " below
Winter North Atlantic	Not assigned	

This Certificate remains in force till the 4th April 1947 on the arrival of New Certificate from the U.K.

B. S. M. S. L.
SURVEYOR TO LLOYD'S REGISTER,
CALCUTTA.

5th April 1946



© 2020

Lloyd's Register
Foundation