

M.S. "NYON".

Uitrustingsnummer.

L = 437,7'
B = 57,3'
D = 37,06'
T = 24,83'

$$EN = 437,7 (57,3 + 24,83) + 0,85 \times 437,7 (37,06' - 24,83).$$
$$= (437,7 \times 82,13) + 0,85 \times 437,7 \times 12,23$$

$$35948,3 + 0,85 \times 5353,071$$
$$35948,3 + 4550,11 = 40498,41$$

$$Bak 0,85 l \times h = 0,85 \times 35,5 \times 7 = 211,23$$

Dekhuizen
Shelterdek 0,75 l x h =
Brugdek 0,75 x 35,75 x 8 = 214,50
Comm.Brugdek 0,75 x 32 x 8 = 192,--
Shelterdek 0,75 x 64 x 8 = 384,--

$$985,50$$
$$EN = 41695,14$$

3 stoklose boegankers elk 69½ cwt.
300 vadem damanketting 2.1/16" (spec.steel)
120 vadem staaldraad 5"
4 x 100 vadem staaldraad 3.1/4".

CLASS: LLOYD'S REGISTER 100.A1. +.

PRINCIPAL DIMENSIONS:

LENGTH BETWEEN P.P.	437' 8½"	133,413 m.
BREADTH MOULDED	57' 3½"	17,462 m.
DEPTH TO UPPERDECK	37' 0"	11,277 m.
DEPTH TO MAINDECK	28' 0"	8,534 m.
DRAUGHT	24' 9"	7,544 m.

$$\frac{L}{D} = 11,81$$

$$\frac{D}{B} = 0,67$$

$$L = 437,7' \quad B = 57,29' \quad D = 37,06' \quad d = 24,83'$$

BRACKET FLOOR.

The scantlings as shown and amended are suitable for a summer draught measured from top of keel of ABOUT 7,529 metres

SECTION AT HOLD II.

UPPERDECK PLATING.

STRINGERPLT. 9/16" A.E. 930x10 7/8"
DECKPLATING 9/16" A.E. 8 1/2%
PLATING ABREAST OPENINGS 18%
PLATING INSIDE LINE OF OPENINGS 9 1/2%.

See longitudinal section for riveted doubler 7/16" x 18 mm.

MAINDECK PLATING

DECKPLATING 9/16" A.E. 9 1/2%
PLATING ABREAST OPENINGS 10%
PLATING INSIDE LINE OF OPENINGS 7 1/2%.

DOUBLE BOTTOM.

CENTRE GIRDER 9/16" A.M.D.S.H.P. 1075x13 1/2". O.I.L. A.E. 11%
SIDE GIRDERS IN HOLDS 9 1/2". MARGINPLATE 950x13 1/2%
FLOORS IN HOLDS 10 1/2%
MIDDLE LINE STRAKE 9/16" A.M.D.S.H.P. 1320x13 1/2". O.I.L. A.E. 10 1/2%
INNER BOTTOM PLATING 9/16" A.M.D.S.H.P. 11 1/2". O.I.L. A.E. 9 1/2%
INNER BOTTOM PLATING UNDER THE HATCHWAYS 13 1/2%
FLOORS IN PEAK 11 1/2%.

CROSS SECTION.

N.V. BOELE'S SCHEEPSWERVEN EN MACHINEFABRIEK
BOLNES HOLLAND

SCHAAL 1:25	DATUM	AFD SCHEEPSBOUW	TEKENING N°
GET: K		BESTEMMING:	© 2020
GEZ:		M.S. "NYON".	R. 770-3
			Lloyd's Register Foundation

003605-003610-0193

MS. " ' NYON ' "

10 ACCOMPANY Rpt. No. 47734.

Dated 20/7/59

SUBJECT: Midship Section
(Ship lengthened).

003605-003610-0193



© 2020

Lloyd's Register
Foundation