

February 10, 1939.

S.S. "PENETANG"

The minimum legal freeboard for this ship is 2'8 $\frac{1}{2}$ " with a corresponding intermediate line of 3'1" and a winter line of 3'5", but due to scantlings the freeboard to centre of diamond should not be less than 3'7 $\frac{1}{2}$ ".

An all seasons freeboard of 3'7 $\frac{1}{2}$ " has therefore been assigned.

Hatch beams to be reinforced.

Lifelines to be fitted.

Closing arrangements for ventilators to be provided where necessary.

Closing arrangements for air pipes to be provided where necessary.

Doors aft to be plated over or cover to be fitted to open stairway.



© 2021

Lloyd's Register
Foundation

003620-003624-0151