

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

29 MAY 1936

Date of writing Report 26 May 1936 When handed in at Local Office 19 Port of Amsterdam

No. in Survey held at Amsterdam Date, First Survey 23 Jan Last Survey 13 May 1936

Reg. Book. on the Single Screw Motor vessel "MACONA" (Number of Visits 20)

Built at Amsterdam By whom built N.V. De Nederlandsche M.Y. Yard No. 235 Tons { Gross 8011 Net 4767

Owners N.V. Petroleum M.Y. "La Corona" Port belonging to 's Gravenhage

Electric Light Installation fitted by N.V. Groeneweld Vander Polder & Co Contract No. When fitted 1936

Is the Vessel fitted for carrying Petroleum in bulk Yes

System of Distribution Double wire

Pressure of supply for Lighting 110 volts, Heating 110 volts, Power 110 volts.

Direct or Alternating Current, Lighting Direct current Power Direct current

If alternating current system, state frequency of periods per second

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding rating Yes, are they compound wound Yes

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel no, is an adjustable regulating resistance fitted in

series with each shunt field Yes

Are all terminals accessible, clearly marked, and furnished with sockets Yes, are they so spaced or shielded that they cannot be accidentally earthed,

short circuited, or touched Yes Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators In engine room on S.B. side

is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

none and, are the generators protected from mechanical injury and damage from water, steam or oil Yes

are their axes of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and

their respective generators in metallic contact Yes

Main Switch Boards, where placed in Motor room on S.B. side

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards none and

are they constructed wholly of durable, non-ignitable non-absorbent materials Yes, is all insulation of high dielectric strength and of

permanently high insulation resistance Yes, if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework none

and is the frame effectively earthed Yes Are the fittings as per Rule regarding:— spacing or shielding of live parts

Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, proportion of omnibus

bars Yes, individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Double Pole Handle Switches

Instruments on main switchboard 2 ammeters 2 voltmeters synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Two lamps in series connected with the earth

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes

Cables: Single, twin, concentric, or multicore ☒ are the cables insulated and protected as per Tables IV, V, XI or XIII of the Rules *yes*

Fail of Pressure, state maximum between bus bars and any point of the installation under maximum load *2 volts for light & 5 V for power*

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets *yes*

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *none*

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *yes*

Support and Protection of Cables, state how the cables are supported and protected *Shel plates and fixed with galvanised iron clips and brass screws*

If cables are run in wood casings, are the casings and caps secured by screws *yes*, are the cap screws of brass *yes*, are the cables run in separate grooves *yes*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *yes*

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *yes*

Joints in Cables, state if any, and how made, insulated, and protected *no joints*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *watertight glands*

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *yes* state the material of which the bushes are made *Lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas

are their connections made as per Rule

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *yes*

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *none*

Navigation Lamps, are these separately wired *yes*, controlled by separate switch and separate fuses *yes*, are the fuses double pole *yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *yes*, has each navigation lamp an automatic indicator as per Rule *yes*

Secondary Batteries, are they constructed and fitted as per Rule *none*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes*, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *none*

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *two lamps in pumproom protected by gas tight lock up boxes outside the pumproom protected by tubes*, how are the cables led

where are the controlling switches situated *on Navigation board*

Searchlight Lamps, No. of *none*, whether fixed or portable ☒, are their fittings as per Rule *c*

Are Lamps, other than searchlight lamps, No. of *none*, are their live parts insulated from the frame or case *c*, are their fittings as per Rule *c*

Motors, are their working parts readily accessible *yes*, are the coils self-contained and readily removable for replacement *yes*, are the brushes, brush holders, terminals and lubricating arrangements as per Rule *yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *yes*, are they protected from mechanical injury and damage from water, steam or oil *yes*, are their axes of rotation fore and aft *yes*, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *none*, if not of this type, state distance of the combustible material horizontally or vertically above the motors *c* and

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *yes*

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *yes*

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *yes*

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *yes*

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Amps.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN	1	16	110	146	390	Diesel engine	Crude oil	above 150°F	
AUXILIARY	1	16	110	146	390	Steam engine			
EMERGENCY									
ROTARY TRANSFORMER									

GENERATOR, LIGHTING AND HEATING CONDUCTORS.									
DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR	1	95	19	2.53	146	150	16 Mils	Rubber lead covered & armoured	
EQUALISER CONNECTIONS									
AUXILIARY GENERATOR	1	95	19	2.53	146	150	10		
EMERGENCY GENERATOR									
ROTARY TRANSFORMER									
MOTOR GENERATOR									
ENGINE ROOM	1	10	7	1.35	25	40	30		
BOILER ROOM									
AUXILIARY SWITCHBOARDS									
Distribution Boxes	1	35	19	1.53	70	78	50		
Sockets aft	1	10	7	1.35	20	40	30		
ACCOMMODATION Aft Port	1	10	7	1.35	10	40	70		
" " SB	1	10	7	1.35	10	40	30		
Amidship	1	16	7	1.70	36	40	170		
Fore Ship	1	16	7	1.70	10	40	350		
Navigation	1	10	7	1.35	35	40	190		
"	1	16	7	1.70	37	40	180		
WIRELESS	1	35	19	1.53	70	78	300		
SEARCHLIGHT	1	1.5	1	1.38	0.5	10	120		
MASTHEAD LIGHT	1	1.5	1	1.38	0.5	10	60		
SIDE LIGHTS	1	1.5	1	1.38	0.5	10	60		
COMPASS LIGHTS	1	1.5	1	1.38	0.5	10	60		
POOP LIGHTS	1	1.5	1	1.38	0.5	10	170		
CARGO LIGHTS									
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.										
DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP	1	1	50 Mils	19	1.00	100	125	22 Mils	Rubber lead covered & armoured	
ENGINE TURNING GEAR										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR										
WORKSHOP MOTOR										
VENTILATING FANS	1	1	250	1	1.78	12	15	50		
Thumpump	1	1	250	1	1.78	8	15	10		
Oil Separator	1	1	4	7	0.85	16	20	52		
Drill	1	1	4	7	0.85	16	20	10		
Rathe	1	1	2.5	1	1.78	12	15	0		
Grinding	1	1	6	7	1.05	24	30	0		

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
The foregoing is a correct description.

N.V. Groeneveld, Van der Poll & Co's

[Signature]

Electrical Engineers.

Date

COMPASSES.

Distance between electric generators or motors and standard compass 75 M

Distance between electric generators or motors and steering compass 73 M

The nearest cables to the compasses are as follows:—

A cable carrying 0.1 Amperes 2 Meters feet from standard compass 2 Meters feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes

The maximum deviation due to electric currents was found to be nihil degrees on course in the case of the standard compass, and nihil degrees on course in the case of the steering compass.

Builder's Signature.

Date

Is this installation a duplicate of a previous case Yes If so, state name of vessel H.V. Rotula No. 13 434

General Remarks (State quality of workmanship, opinions as to class, &c.)

The installation has been constructed under Special Survey to approved plans in accordance with the Society's rules and Secretary's letters Material & workmanship good
Tested installation under full working condition found good

W. L. J.
8/6/36.

Total Capacity of Generators 32 Kilowatts.

The amount of Fee ...

£ 276

When applied for,

19

Travelling Expenses (if any) £

When received,

6. 6. 36

19

[Signature]
Surveyor to Lloyd's Register of Shipping.

Committee's Minute

FRI. 12 JUN 1936

Assigned

See other Nos 76 13698



© 2020

Lloyd's Register
Foundation