

11 NOV 1958

Chief Ship Surveyor

Received from Chief Ship Surveyor

AME "OVULA"
AR.

REPORT Sng. 12884.
No.

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/52.)

There is an S.R.L. APPENDIX note.

A SPECIAL SURVEY (C) becomes due 7,59.

The Singapore Surveyors report (9.58) this ship examined in drydock and the requirements of an Annual Survey complied with.

In accordance with Circular No: 2106 and at the Owner's request this ship has been generally examined and the thicknesses of shell, decks, bulkheads and internals as ascertained by drilling are embodied on separate plans attached to this Report.

On account of wear and tear, repairs effected to shell plates B.4 & 5 (p & s.f).

The Surveyors further report 75 fathoms of chain cable renewed (worn) and verified with Certificates (see Rpt. 8(Eq) attached).

IT IS SUBMITTED record of 'DS 8,58' be assigned as recommended.
DS 8,58.

S.R.L. APPENDIX.

Forecastle sheerstrake plate (s.s) buckled.

Indents in shell plating (p & s).

Recommended shell & deck renewals have been indicated on the plans submitted.

IT IS FURTHER SUBMITTED this Report should be sent to Ship Research Dept. for consideration of shell and deck thicknesses (after Committee) in order that the Owners may be advised of the extent of anticipated repairs for the S.S.

With respect to the wasted internal structure, the Singapore Surveyors should be further advised that (after consideration by Ship Research Dept) the recommended repairs for this should be readily dealt with by them per our previous instructions in similar cases, and for their general guidance be advised that where the ~~diminution~~ thickness of the individual internal items are reduced by approx. 30% of the original thickness they should be renewed.

Thicknesses.



Lloyd's Register
Foundation

003659-003670-0088

Toward plans of renewals to Singapore
Surveyors for their perusal to request
return of plans indicating renewals of
shell & deck plating only, after ~~for~~ noting,
for reference in this office

53



© 2020

Lloyd's Register
Foundation