

COPY.

G.O.

Lloyd's Register of Shipping.



Port Copenhagen

Class Contemp^d

18th March, 1935.

This is to Certify that

S. Sandersen

the undersigned Surveyor to this Society did at the request of H. Rask Petersen, Esq., Lloyd's Agent, Odense, and with the consent of Messrs. Odense Staalskibsværft A/S, Odense, on the 25th January 1935 and subsequent dates survey the m.s. "PERNA", (yard newbuilding No. 54) without prejudice to the various interests concerned, while the vessel was afloat alongside the yards outfitting quay for the purpose of ascertaining the nature and extent of damage stated to have been sustained through fire onboard on the 24th January, 1935.

On examination the undersigned

Found:-

,Recommended:-

Saloon house:-

5 sidelights of metal with dead- To be renewed.
lights and glasses in way of
saloon damaged.

3 glasses for sidelights and 2 To be renewed.
fixed glassed in skylight broken.

"Dermas" deck covering in way of To be renewed.
saloon damaged by water and heat.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for accuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society."

003659-003670-0134 15

Found:-

Recommended:-

O.P. wood deck in port passage
and in part of the cabins in way
damaged by fire.

To be renewed.

O.P. wood deck in starboard
passage damaged by water and
smoke.

To be planed and recaulked.

Wood bulkheads, wood linings etc.
partly damaged by fire, smoke or
water.

To be renewed where damaged.

Panels, furniture etc. in saloon
and cabins etc. partly damaged by
fire, smoke or water.

To be renewed or cleaned
and repolished as necessary.

10 plywood doors and 1 teak door
with frames damaged by fire and
water.

To be renewed.

Ice chest in pantry damaged by
smoke and water.

To be repaired, mountings
to be replated and chest to
be repainted.

Hot press in pantry damaged by
smoke and water.

Top part to be renewed.

Metal screen for radiator in
saloon damaged by fire.

To be renewed.


Boat deck:-

9 deck beams buckled.

To be renewed.

Tie plates in way buckled.

To be renewed.



© 2020

Lloyd's Register
Foundation

0134 215

Found:-

Recommended:-

Deck plates in front of
Captain's house buckled.
Foundation angle bars in
way of deck house and front
bulwark set down.

To be renewed.

P. wood deck outside the
Captain's house partly damaged
by fire.

To be renewed where damaged.

P. wood deck inside the
Captain's house damaged by
fire.

To be renewed.

tiles and cement in Captain's
bathroom etc. damaged by heat
and water.

To be renewed.

Captain's house:-

front plates buckled due
to beam having sagged.

To be taken out, faired and
replaced.

front plates in way slightly
buckled.

To be faired in place.

polished hard wood doors
damaged by smoke and water.

To be renewed.

teak doors with frames
damaged by smoke.

To be cleaned and revarnished.

wood bulkheads, linings etc.
partly damaged by smoke and
water.

To be renewed where damaged.



© 2020

Lloyd's Register
Foundation

0134 315

Found:-

Panels, furniture etc. damaged
by smoke and water.

Chart- & wheel house:-

Furniture damaged by smoke.

Wood lining and doors damaged
by smoke.

Electric installation:-

Cables, switches, fuse boxes,
fittings etc. in way of mid-
ships accommodation partly
damaged by fire and water.

Panels with instruments, boxes
etc. partly damaged by smoke
and water.

Sanitary installation:-

Pipes with fittings partly
damaged by fire.

Fittings for baths, wash
basins etc. damaged by smoke.

6 wash basins damaged by heat
and smoke.

Recommended:-

To be renewed or cleaned
and repolished as necessary.

To be cleaned and repolished.

To be cleaned and revarnished.

To be fully renewed.

To be taken down, overhauled
and renewed as necessary and
tested after repairs.

All pipes with fittings in way
of the midships accommodation
to be overhauled and renewed
where necessary and tested after
repair.

To be cleaned, overhauled and
replated where necessary.

To be renewed.



© 2020

Lloyd's Register
Foundation

0134 4/5

Found:-

Recommended:-

Telemotor- & telegraph lines:-

Pipes with fittings, rods, chains, wheels etc. partly damaged by fire and water.

To be taken adrift, examined, renewed where damaged and tested after being refitted.

Telemotor, telegraph and compass house in the wheel house partly damaged by smoke.

To be cleaned, examined, adjusted and repolished.

Heating arrangement:-

Radiators with fittings partly damaged by heat and water.

To be taken down, renewed or repacked where damaged and tested.

Pipes with fittings etc. partly damaged by heat and water.

To be overhauled, renewed where damaged and retested.

Painting:-

Painting of houses, accommodation, decks etc. (inside and out-where necessary and repainted side) partly damaged by heat or smoke.


To be cleaned, scraped off to the same extend as before the damage was sustained.

Further recommended that all necessary removals be replaced, and (where damaged in course of above repairs) repaired or renewed as necessary, the repairs suitably coated on completion of work.

These recommendations made so as to place the vessel in the same condition as before the damage was sustained.

Fees:- 345,00 Kr.

Expenses:- 150,00 Kr.



SURVEYOR TO LLOYD'S
REGISTERED

Lloyd's Register
Foundation

0134 515

Expenses:- 150,00 Kr.
Fees:- 345,00 Kr.

2 2

© 2020 Lloyd's Register Foundation

In the same condition as before the damage was sustained.

These recommendations made so as to place the vessel on completion of work.

Repaired or renewed as necessary, the repairs suitably coated be replaced, and (where damaged in course of above repairs)

Further recommended that all necessary removals

smoke.

the damage was sustained.

side) partly damaged by heat or to the same extent as before
tion, decks etc. (inside and out-where necessary and repainted
Painting of houses, accommoda- To be cleaned, scraped off
Painting:-

ly damaged by heat and water.

damaged and retested.

pipes with fittings etc. part-

To be overhauled, renewed where

tested.

ly damaged by heat and water.

repacked where damaged and

Radiators with fittings part-

To be taken down, renewed or

Heating arrangement:-

house partly damaged by smoke.

tested and repolished.

compass house in the wheel

To be cleaned, examined, ad-

damaged by fire and water.

after being refitted.

chains, wheels etc. partly

renewed where damaged and tested

pipes with fittings, rods,

To be taken apart, examined,

Telemotor & telegraph lines:-

Found:-

Recommended:-