

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.  
Lloyd's Register.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.

Signal Letters (if any) G. W. G. F.

Official Number.		Name of Ship.	No., Date, and Port of Registry.		
163,166.		Basque.	53/1933. Hull.		
No., Date, and Port of Previous Registry (if any). -----					
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Screw.	Beverley.	1933.	Cook Welton & Gemmell Limited, Beverley.	
Number of Decks .. One & Raised Qr. Deck		Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post .. .. .		Feet.	Tenths.
Number of Masts .. Two				154	6
Rigged .. .. . Ketch		Length at quarter of depth from top of weather deck at side amidships to bottom of keel .. .. .			
Stern .. .. . Cruiser		Main breadth to outside of plank .. .. .		25	6
Build .. .. . Clincher		Depth in hold from tonnage deck to ceiling at midships .. ..		13	9
Galleries .. .. . None		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards .. .. .			
Head .. .. . Straight Stem		Depth from top of beam amidships to top of keel .. .. .		15	4
Framework and description of vessel .. .. . Steel Trawler		Depth from top of deck at side amidships to bottom of keel ..		.	.
Number of Bulkheads .. Five		Round of beam .. .. .			
Number of water ballast tanks, Two and their capacity in tons About 14 tons.		Length of engine room, if any .. .. .		32	6 <sup>3</sup> / <sub>7</sub>

## PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel .. Tons. Ditto per inch immersion at same depth .. Tons.

## PARTICULARS OF PROPELLING ENGINES, &amp;c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
One	Triple Expansion Direct Acting Inverted Cylinder.	Engines.	Engines.	Engines.	Three			N. H. P.
	Particulars of Boilers.	British	1933	C. D. Holmes & Co., Ltd., Hull.	13 <sup>1</sup> / <sub>2</sub> "	27"	-----	111
	Description Cylindrical Multitubular	Boilers.	Boilers.	Boilers.	24 "			I. H. P.
One	Number One Steel	British	1933	C. D. Holmes & Co., Ltd., Hull.	39 "			700
	Iron or Steel							11 <sup>1</sup> / <sub>2</sub> knots
	Loaded Pressure 210 lbs							

## PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ..	372.39	On account of space required for propelling power	192.82
Space or spaces between Decks ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk ..		These spaces are the following, viz. :—	
Forecastle Side Houses under	3.19	Below Dk. fwd.	
Bridge space		---"--- Aft.	48.39
Peep or Break	20.26	(Number of Seamen or Apprentices for whom accommodation is certified.....18.....).	
Side Houses ..	13.57	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Deck Houses		Masters Accommodation 4.34 )	
Chart House		Chart Space 1.05 )	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ..	14.89	Wireless Telegraphy Space 2.53 )	20.77
Excess of Hatchways ..		Boatswain's Store 8.49 )	
Gross Tonnage ..	424.30	Water Ballast Spaces 4.36 )	
Deductions, as per Contra ..	261.98	Total ..	261.98
Register Tonnage ..	162.32		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 95.29 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 14.89 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle L. 25' .2 - 15.06 Tons.

Name of Master	Certificate of	Service Competency	No. No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
Hellyer Bros. Limited, St. Andrew's Dock, Kings ton-upon-Hull. (Sixty-four (64) Shares).	Frank Orlando Hellyer and Owen Stooks Hellyer both same address-Managers-		
Dated 14th November 1933.			